

# PCT

# WORLD INTELLECTUAL PROPERTY ORGANIZATION International Bureau



## INTERNATIONAL APPLICATION PUBLISHED UNDER THE PATENT COOPERATION TREATY (PCT)

(51) International Patent Classification 6:
H04B 7/00
A2
(11) International Publication Number: WO 99/49586
(43) International Publication Date: 30 September 1999 (30.09.99)

(21) International Application Number: PCT/US99/00940

(22) International Filing Date: 15 January 1999 (15.01.99)

(30) Priority Data:

60/071,659 16 January 1998 (16.01.98) US 09/231,228 14 January 1999 (14.01.99) US

(71) Applicant (for all designated States except US): HARRIS CORPORATION [US/US]; 2401 Palm Bay Road, N.E., Palm Bay, FL 32905 (US).

(72) Inventors: and


- (75) Inventors/Applicants (for US only): ANDREN, Carl [US/US]; 906 S. Ramona Avenue, Indialantic, FL 32903 (US). WEBSTER, Mark, A. [US/US]; 1201 Green Court S.E., Palm Bay, FL 32905 (US).
- (74) Agent: WARTHER, Richard, K.; Allen, Dyer, Doppelt, Milbrath & Gilchrist, P.A., Suite 1401, 255 S. Orange Avenue, Orlando, FL 32802-3791 (US).

(81) Designated States: AL, AM, AT, AU, AZ, BA, BB, BG, BR, BY, CA, CH, CN, CU, CZ, DE, DK, EE, ES, FI, GB, GE, GH, GM, HR, HU, ID, IL, IS, JP, KE, KG, KP, KR, KZ, LC, LK, LR, LS, LT, LU, LV, MD, MG, MK, MN, MW, MX, NO, NZ, PL, PT, RO, RU, SD, SE, SG, SI, SK, SL, TJ, TM, TR, TT, UA, UG, US, UZ, VN, YU, ZW, ARIPO patent (GH, GM, KE, LS, MW, SD, SZ, UG, ZW), Eurasian patent (AM, AZ, BY, KG, KZ, MD, RU, TJ, TM), European patent (AT, BE, CH, CY, DE, DK, ES, FI, FR, GB, GR, IE, IT, LU, MC, NL, PT, SE), OAPI patent (BF, BJ, CF, CG, CI, CM, GA, GN, GW, ML, MR, NE, SN, TD, TG).

#### Published

Without international search report and to be republished upon receipt of that report.

(54) Title: SPREAD SPECTRUM TRANSCEIVER FOR USE IN WIRELESS LOCAL AREA NETWORK AND HAVING MULTIPATH MITIGATION



ARCHITECTURE FOR THE VITERBI-DFE

#### (57) Abstract

A method and spread spectrum transceiver for demodulating a spread spectrum signal is disclosed. A spread spectrum phase shift keyed (PSK) modulated information signal is received within a demodulator of a spread spectrum receiver on a signal channel. The information signal includes a sequence of data symbols formed from a plurality of high rate mode chips. A precursor portion of the signal channel is Viterbi detected. A multi-state trellis is formed having a predetermined number of states. A post-cursor potion of the signal channel is feedback equalized with a finite impulse response filter having feedback taps operatively connected to a chip detection circuit that tracks high rate mode chips and a carrier loop circuit for phase and frequency tracking. The information signal is despread within a spread spectrum code function correlator.



# FOR THE PURPOSES OF INFORMATION ONLY

Codes used to identify States party to the PCT on the front pages of pamphlets publishing international applications under the PCT.

AL Albania						
AL Albania	ES	Spain	LS	Lesotho	SI	Slovenia
AM Armenia	FI	Finland	LT	Lithuania	SK	Slovakia
AT Austria	FR	France	LU	Luxembourg	SN	Senegal
AU Australia	GA	Gabon	LV	Latvia	SZ	Swaziland
AZ Azerbaija	GB	United Kingdom	MC	Monaco	TD	Chad
BA Bosnia an	Herzegovina GE	Georgia	MD	Republic of Moldova	TG	Togo
BB Barbados	GH	Ghana	MG	Madagascar	T.J	Tajikistan
BE Belgium	GN	Guinea	MK	The former Yugoslav	TM	Turkmenistan
BF Burkina F	aso GR	Greece		Republic of Macedonia	TR	Turkey
BG Bulgaria	HU	Hungary	ML	Mali	TT	Trinidad and Tobago
BJ Benin	IE	Ireland	MN	Mongolia	UA	Ukraine
BR Brazil	IL	Israel	MR	Mauritania	UG	Uganda
BY Belarus	IS	Iceland	MW	Malawi	US	United States of America
CA Canada	IT	Italy	MX	Mexico	UZ	Uzbekistan
CF Central A	rican Republic JP	Japan	NE	Niger	VN	Viet Nam
CG Congo	KE	Kenya	NL	Netherlands	YU	
CH Switzerlar	d KG	Kyrgyzstan	NO	Norway	zw	Yugoslavia
CI Côte d'Ive	ire KP	Democratic People's	NZ	New Zealand	2**	Zimbabwe
CM Cameroon		Republic of Korea	PL	Poland		
CN China	KR	Republic of Korea	PT	Portugal		
CU Cuba	KZ	Kazakstan	RO	Romania		
CZ Czech Re		Saint Lucia	RU	Russian Federation		
DK Denmark	<del></del>					
_						
DE Germany		LI LK LR	LI Liechtenstein LK Sri Lanka	LI Liechtenstein SD LK Sri Lanka SE	LI Liechtenstein SD Sudan LK Sri Lanka SE Sweden	LI Liechtenstein SD Sudan LK Sri Lanka SE Sweden

WO 99/49586 PCT/US99/00940

SPREAD SPECTRUM TRANSCEIVER FOR USE IN WIRELESS LOCAL AREA NETWORK AND HAVING MULTIPATH MITIGATION

This application is based upon prior filed copending provisional application no. 60/071,659 filed January 16, 1998.

#### Field of the Invention

This invention relates to the field of communication electronics, and more particularly, to a spread spectrum transceiver for use in wireless local area networks.

## Background of the Invention

wireless or radio communication between separated electronic devices is widely used. For example, a wireless local area network (WLAN) is a flexible data communication system that may be an extension to, or an alternative for, a wired LAN within a building or campus. A WLAN uses radio technology to transmit and receive data over the air, thereby reducing or minimizing the need for wired connections.

15 Accordingly, a WLAN combines data connectivity with user mobility, and, through simplified configurations, also permits a movable LAN.

Over the past several years, WLANs have gained acceptance among a number users including, for example, health-care, retail, manufacturing, warehousing, and academic areas. These groups have benefitted from the productivity gains of using hand-held terminals and notebook computers, for example, to transmit real-time information to centralized hosts for processing. Today WLANs are becoming more widely recognized and used as a general purpose connectivity alternative for an even broader range of users. In addition, a WLAN provides installation flexibility and permits a computer network

to be used in situations where wireline technology is not practical.

In a typical WLAN, an access point is provided by a transceiver, that is, a combination transmitter and receiver, connects to the wired network from a fixed location. Accordingly, the access transceiver receives, buffers, and transmits data between the WLAN and the wired network. access transceiver can support a small group of 10 collocated users within a range of less than about one hundred to several hundred feet. The end users connect to the WLAN through transceivers which are typically implemented as PC cards in a notebook computer, or ISA or PCI cards for desktop computers. Of course the 15 transceiver may be integrated with any device, such as a hand-held computer.

Spread spectrum communications have been used for various applications, such as cellular telephone communications, to provide robustness to jamming, good 20 interference and multi-path rejection, and inherently secure communications from eavesdroppers, as described, for example, in U.S. Patent No. 5,515,396 to Dalekotzin. The patent discloses a code division multiple access (CDMA) cellular communication system 25 using four Walsh spreading codes to allow transmission of a higher information rate without a substantial duplication of transmitter hardware. U.S. Patent No. 5,535,239 to Padovani et al., U.S. Patent No. 5,416,797 to Gilhousen et al., U.S. Patent No. 5,309,474 to Gilhousen et al., and U.S. Patent No. 5,103,459 to 30 Gilhousen et al. also disclose a CDMA spread spectrum cellular telephone communications system using Walsh function spreading codes. The disclosures of each of these patents is hereby incorporated by reference in 35 their entirety.

It is possible to reduce multipath problems, such as with GSM cell phones using a Viterbi maximum

15

20

25

likelihood sequence estimation (MLSE). However, applying MLSE is complex for 802.11 high data rate receivers. The Viterbi algorithm, nonetheless, if it could be applied to 802.11 spread spectrum transceivers, could provide a beneficial way to attack the multipath problem, especially if used in combination with other sources of equalization.

Viterbi encoders and detectors have been used in various electronic and digital uses, including digital communication channels, such as disclosed in U.S. Patent No. 5,774,504, and the systems and circuits as disclosed in U.S. Patent Nos. 5,841,819 and 5,844,741, the disclosures which are hereby incorporated by reference in their entirety.

The assignee of the present invention has used Viterbi algorithm and decoders, such as disclosed in U.S. Patent Nos. 4,545,054 and 4,346,473, the disclosures which are hereby incorporated by reference in their entirety.

#### Summary of the Invention

It is therefore an object of the present invention to provide a spread spectrum transceiver having a base band processor and demodulation that may use the Viterbi algorithm with feedback equalization.

In accordance with the present invention, a method of the present invention demodulates a spread spectrum signal and comprises the steps of receiving within a demodulator of a spread spectrum receiver, a spread spectrum phase shift keyed (PSK) modulated 30 information signal on a signal channel. information signal includes a sequence of data symbols formed from a plurality of high rate mode chips. method also comprises the step of Viterbi decoding a precursor portion of the signal channel and forming a 35 multi-state trellis having a predetermined number of states. The method also comprises the step of feedback equalizing a post-cursor portion of the signal channel

with a finite impulse response filter having feedback taps operatively connected to a chip detector circuit that tracks high rate mode chips and a carrier loop circuit for phase and frequency tracking. also comprises the step of despreading the information signal within the spread spectrum code function correlator.

In still another aspect of the present invention, the method comprises the step of performing a partial signal trace back of the multi-state trellis to the feedback taps of the finite impulse response filter. The method also comprises the step of passing a signal trace back from a Viterbi detector circuit to the spread spectrum code function correlator. 15 method also includes a sequence of data symbols formed from a plurality of high rate mode chips. The signal channel forms a finite state machine and further comprises the step of establishing a predetermined number of states within the multi-state trellis.

20 In accordance with the present invention, a spread spectrum radio transceiver is disclosed and includes a base band processor and radio circuit connected thereto. The base band processor includes a demodulator for spread spectrum phase shift keying 25 (PSK) demodulating an information signal on a signal channel. The information signal includes data symbols formed from a plurality of high rate mode chips forming a spread spectrum information signal. The demodulator comprises at least one spread spectrum code function correlator for decoding the information according to a 30 predetermined orthogonal code sequence. A Viterbi decoder receives the information signal and decodes a precursor portion of the signal channel. A carrier loop circuit allows for phase and frequency tracking of 35 the information signal. A chip decision circuit is operative with a carrier loop circuit and tracks high rate chips.

A decision feedback equalizer is formed from a finite impulse response filter and operative with the chip decision circuit and carrier loop circuit. equalizer has a plurality of feedback taps and at least 5 one feedback tap is selected for logical add/subtract operations for equalizing a post-cursor portion of the signal channel. A modulator spread spectrum PSK modulates information for transmission via the radio circuit. The modulator comprises at least one code 10 function encoder for encoding information according to an orthogonal code sequence. The at least one spread spectrum code function correlator comprises a Walsh correlator. The Viterbi decoder can further comprise means for generating a trace back soft decision to the spread spectrum code function correlator. The Viterbi decoder can further comprise means for generating a partial trace back to predetermined feedback paths of the finite impulse response filter. The carrier loop circuit can also include a carrier numerically 20 controlled oscillator (NCO). A carrier NCO control circuit selectively operates the carrier NCO based upon a carrier phase of the carrier loop circuit.

# Brief Description of the Drawings

Other objects, features and advantages of the
present invention will become apparent from the
detailed description of the invention which follows,
when considered in light of the accompanying drawings
in which:

FIGS. 1A-1F illustrate a spread spectrum
transceiver with associated components, which with
modifications, can be used for the present invention,
wherein:

FIG. 1A shows the basic circuit components of a spread spectrum transceiver.

FIG. 1B is a schematic circuit diagram of a modulator portion of a high data rate base band

20

30

35

processor that can be used with modifications with the present invention.

FIG. 1C is a timing diagram of signals that can be generated by the circuits shown in FIGS. 1A and 1B.

FIG. 1D is a timing diagram of additional signals that can be generated by the circuits of FIGS. 1A and 1B.

FIG. 1E is a schematic circuit diagram of a 10 demodulator portion of the base band processor shown in FIG. 1A.

FIG. 1F is a schematic circuit diagram of a correlator portion of the demodulator of FIG. 1A.

FIG. 1G is a block diagram of components

15 illustrating how a waveform for M-ary orthogonal keying

(MOK) can be generated.

FIG. 1H illustrates four modulation modes of an extended modulation package.

FIGS. 2-5 illustrate the correlation of noncoherent bit sync metric of the present invention with the Walsh distance shown for 10, 25, 50 and 100 ns RMS.

FIG. 6A illustrates a code set diversity high rate frame format that includes a code set high rate portion within the message so that the decision is improved by not being based purely on the Barker

25 improved by not being based purely on the Barker portion of a waveform.

FIG. 6B illustrates another code set high rate field format where the implementation scheme assumes that the decision is purely made on the Barker code without any feedback from the Walsh/CCK part of the message.

FIG. 6C is a block circuit diagram of a portion of the demodulator circuit in FIG. 1A that determines bit sync peak sample and subtracts a predetermined number of bit sync samples.

20

35

rate.

1

FIG. 7 illustrates a block diagram showing key system components that induce end-to-end linear distortion.

FIG. 8 is a block diagram showing linear 5 distortions for transmit and receive filters.

FIGS. 9A and 9B show the respective frequency response and impulse response for real SAW filter characteristics and showing a third transit echo.

FIGS. 10A and 10B show end-to-end mode and 10 filter responses.

FIG. 11 is a graph showing the discrete exponentially-decaying Raleigh fading channel model.

FIGS. 12A and 12B show the exponential fading example for a stochastic realization for a 100 nsec RMS delay-spread case.

FIGS. 13A, 13B and 13C show the respective impulse response, frequency response and Nyquist bandwidth and the corresponding constellation for a modem/channel cascade example for a stochastic realization for the 100 nsec RMS delay spread.

FIGS. 14A and 14B show the respective impulse response and frequency response for a stochastic realization with a 200 nsec RMS delay spread.

FIG. 15 illustrates a graph of a post cursor 25 component.

FIG. 16 illustrates how the signal power in a spread spectrum receiver is influenced by the communication link.

FIG. 17 illustrates an ideal AGC set-up 30 position.

FIG. 18 illustrates various viewpoints that dominate high-rate 802.11 signaling.

FIG. 19 is a graph illustrating a digital modulations capacity comparison at  $10^{-5}$  symbol error

FIG. 20 is a chart illustrating cellular/PCS signaling paradigms.

FIG. 21 is a graphical chart illustrating how the ISI is minimized by increasing symbol duration so the convolution smear is a small percentage of the symbol.

FIG. 22 is a graph illustrating good correlation properties that consume bandwidth.

FIG. 23 illustrates key advantages using chip-level equalization.

FIG. 24 is a graph illustrating a comparison of the symbol error rate with the symbol level versus chip level processing.

FIG. 25 is a chart illustrating equalizer performance comparisons.

FIG. 26 is a simplified block diagram for the demodulator architecture that is generically shown in FIGS. 1A-1F.

FIG. 27 is a graph showing the multipath performance for the architecture shown in FIG. 26.

FIG. 28 is a circuit block diagram of a 20 decision feedback equalizer that can be used in the present invention, and illustrating a feed-forward section and a feedback section.

FIG. 29 is a graph illustrating a typical end-to-end impulse response at 100 nsec RMS.

FIG. 30 is a graph illustrating channel zeros for the impulse response shown in FIG. 29.

FIG. 31 is a channel diagram emphasizing typical characteristics of multipath.

FIG. 32 illustrates a two tap feed-forward 30 DFE ZF weight calculation.

FIG. 33 is a schematic block diagram showing feedback taps only for the demodulation architecture of the spread spectrum demodulator.

FIG. 34 is a graph illustrating the packet error rate performance in multipath for various feedback tap quantities.

FIG. 35 is a schematic block diagram of a demodulator architecture that includes feed forward DFE taps.

FIG. 36 is a graph illustrating the packet error rate performance and multipath for two feed forward taps and various feedback tap quantities.

FIG. 37 is a graph illustrating the packet error rate performance and multipath for three feed forward taps and various feedback taps quantities.

10 FIG. 38A illustrates a finite state machine channel viewpoint with a channel impulse response that forms FSM and FIG. 38B represents a representative trellis.

FIG. 39 illustrates how the complexity of the finite-state-machine can be reduced through decision feedback.

FIG. 40 is a diagram of a trellis that illustrates a partial traceback used to feed a decision feedback stage.

FIG. 41 is a graph illustrating a viterbi DFE performance variation with increasing partial traceback delays.

FIG. 42 is a schematic block diagram illustrating a demodulator architecture for the viterbi/DFE.

FIG. 43 is a graph showing a multipath-spread performance curves for four state viterbi/DFE.

FIG. 44 is a graph illustrating the multipath-spread performance curves for 16 state viterbi/DFE.

FIG. 45 is a chart illustrating packet error rate performance for various RMS multipath spread with different taps.

FIG. 46 is a basic DFE structure with map 35 operation/chip.

FIG. 47 illustrates a gate count complexity for two feed forward taps and six feedback taps DFE.

20

25

30

FIG. 48 is a channel impulse response showing amplitude and phase information.

## Detailed Description of the Preferred Embodiments

The present invention will now be described

more fully hereinafter with reference to the
accompanying drawings, in which preferred embodiments
of the invention are shown. This invention may,
however, be embodied in many different forms and should
not be construed as limited to the embodiments set

forth herein. Rather, these embodiments are provided
so that this disclosure will be thorough and complete,
and will fully convey the scope of the invention to
those skilled in the art. Like numbers refer to like
elements throughout.

## General Technical Background

For purposes of description and understanding, a basic spread spectrum radio transceiver is described in detail below to give a technical background of the present invention. The spread spectrum transceiver and related information as described relative to FIGS. 1A-1H, concerns a basic spread spectrum radio transceiver with a high rate capability used in a wireless local area network. Naturally, the present invention is not limited to such a transceiver, which only is illustrated and described for purposes of technical understanding. Such a transceiver is described further in U.S. Patent application serial no. 08/819,846 filed March 17, 1997, by the present assignee, the disclosure which is hereby incorporated by reference in its entirety.

Referring to FIG. 1A, a basic wireless transceiver 30 is shown that can be modified in accordance with the present invention. The transceiver 30 may be readily used for WLAN applications in the 2.4 GHz ISM band in accordance with the proposed IEEE 802.11 standard. The transceiver 30 includes

WO-99/49586 PCT/US99/00940

-11-

selectable antennas 31 coupled to the radio power amplifier and TX/RX switch 32 as may be provided by a Harris part number HFA3925. As would be readily understood by those skilled in the art, multiple antennas are provided for space diversity reception.

A low noise amplifier 38, as may be provided by Harris part number HFA3424, is also operatively connected to the antennas. The illustrated up/down converter 33 is connected to both the low noise amplifier 38 and the RF power amplifier and TX/RX switch 32 as would be readily understood by those skilled in the art. The up/down converter 33 may be provided by a Harris part number HFA3624, for example. The up/down converter 33, in turn, is connected to the illustrated dual frequency synthesizer 34 and the quad IF modulator/demodulator 35. The dual synthesizer 34 may be a Harris part number HFA3524 and the quad IF modulator 35 may be a Harris part number HFA3724. All the components described so far are included in a 2.4 20 GHz direct sequence spread spectrum wireless transceiver chip set manufactured by Harris Corporation under the designation PRISM 1. Various filters 36, and the illustrated voltage controlled oscillators 37 may also be provided as would be readily understood by 25 those skilled in the art and as further described in the Harris PRISM 1 chip set literature, such as the application note No. AN9614, March 1996, the entire disclosure of which is incorporated herein by reference.

Turning now more particularly to the right hand side of FIG. 1A, a high data rate direct sequence spread spectrum (DSS) baseband processor 40 is now described. The conventional Harris PRISM 1 chip set includes a low data rate DSS baseband processor

available under the designation HSP3824. This prior baseband processor is described in detail in a publication entitled "Direct Sequence Spread Spectrum Baseband Processor, March 1996, file number 4064.4, and the entire disclosure of which is incorporated herein by reference.

Like the HSP3824 baseband processor, the high data rate baseband processor 40 of the invention contains all of the functions necessary for a full or 10 half duplex packet baseband transceiver. The processor 40 has on-board dual 3-bit A/D converters 41 for receiving the receive I and Q signals from the quad IF modulator 35. Also like the HSP3824, the high data rate processor 40 includes a receive signal strength 15 indicator (RSSI) monitoring function with the on-board 6-bit A/D converter and CCA circuit block 44 provides a clear channel assessment (CCA) to avoid data collisions and optimize network throughput as would be readily understood by those skilled in the art.

An extension of the PRISM 1 product from 1
Mbit/s BPSK and 2 Mbit/s QPSK to 5.5 Mbit/s BPSK and 11
Mbit/s QPSK is provided. This is accomplished by
keeping the chip rate constant at 11 Mchip/s. This
allows the same RF circuits to be used for higher data
rates. The symbol rate of the high rate mode is 11
MHZ/8 = 1.375 Msymbol/s.

As an example, the 5.5 Mbit/s mode, the bits are scrambled and then encoded from 4 bit nibbles to 8 chip modified Walsh functions. This mapping results in bi-orthogonal codes which have a better bit error rate (BER) performance than BPSK alone. The resulting 11 Mchip/s data stream is BPSK modulated. The demodulator comprises a modified Walsh correlator and associated chip tracking, carrier tracking, and reformatting devices as described in greater detail below.

30

For the 11 Mbit/s mode, the bits are scrambled and then encoded from 4 bit nibbles to 8 chip modified Walsh functions independently on each I and Q rail. There are 8 information bits per symbol mapped to 2 modified Walsh functions. This mapping results in bi-orthogonal codes which have better BER performance than QPSK alone. The resulting two 11 Mchip/s data streams are QPSK modulated.

The theoretical BER performance of this type

of modulation is approximately 10<sup>-5</sup> at an Eb/No of 8 dB

versus 9.6 dB for plain BPSK or QPSK. This coding gain
is due to the bi-orthogonal coding. There is bandwidth

expansion for all of the modulations to help combat

multi-path and reduce the effects of interference.

Referring additionally to FIG. 1B, the output 15 of the QPSK/EPSK modulator and scrambler circuit 51 is partitioned into nibbles of Sign-Magnitude of 4 bits, with the least significant bit (LSB) first. For QPSK, 2 nibbles are presented in parallel to the Modified 20 Walsh Generators 53a, 53b -- the first nibble from the B serial-in/parallel-out SIPO circuit block 52b and the second from A SIPO 52a. The two nibbles form a symbol of data. The bit rate may be 11 Mbit/s as illustrated. Therefore, the symbol rate is 1.375 Mbit/s 1.375). For BPSK, nibbles are presented from the A 25 SIPO 52a only. The B SIPO 52b is disabled. A nibble The bit rate in this instance forms a symbol of data. is 5.5 Mbit/s and the symbol rate remains 1.375 Mbit/s (5.5/4 = 1.375).

The Magnitude part of the SIPO output points to one of the Modified Walsh Sequences shown in the table below, along with the basic Walsh sequences for comparison.

	MAG	BASIC WALSH	MODIFIED WALSH
35	0	00	03
	1	OF	0C
	2	33	30

WO 99/49586

15

-14-

	3	3C	3F
	4	55	56
	5	5A	59
	6	66	65
5	7	69	6A.

The Sel Walsh A, and Sel Walsh B bits from the clock enable logic circuit 54 multiplex the selected Walsh sequence to the output, and wherein the LSBs are output first. The A Sign and B Sign bits bypass the respective Modified Walsh Generators 53a, 53b and are XOR'd to the sequence.

As would be readily understood by those skilled in the art, there can be other possible mappings of bits to Walsh symbols. In addition, the Modified Walsh code may be generated by modulo two adding a fixed hexadecimal code to the basic or standard Walsh codes to thereby reduce the average DC signal component and thereby enhance overall 20 performance.

The output of the Diff encoders of the last symbol of the header CRC is the reference for the high rate data. The header may always be BPSK. reference is XOR'd to I and Q signals before the 25 output. This allows the demodulator 60, as described in greater detail below, to compensate for phase ambiguity without Diff decoding the high rate data. Data flip flops 55a, 55b are connected to the multiplexer, although in other embodiments the flip 30 flops may be positioned further downstream as would be readily understood by those skilled in the art. output chip rate is 11 Mchip/s. For BPSK, the same chip sequence is output on each I and Q rail via the multiplexer 57. The output multiplexer 58 provides the selection of the appropriate data rate and format.

Referring now additionally to FIG. 1C, a timing and signal format for the interface 80 is

described in greater detail. Referring to the left hand portion, Sync is all 1's, and SFD is F3AOh for the PLCP preamble 90. Now relating to the PLCP header 91, the SIGNAL is:

5	OAh	1 Mbit/s BPSK,
	14h	2 Mbit/S QPSK,
	37h	5.5 Mbit/s BPSK, and
····· .	6Eh	11 Mbit/s QPSK.

10 The SERVICE is OOh, the LENGTH is XXXXh wherein the length is in  $\mu$ s, and the CRC is XXXXh calculated based on SIGNAL, SERVICE and LENGTH. MPDU is variable with a number of octets (bytes).

The PLCP preamble and PLCP header are always at 1 Mbit/s, Diff encoded, scrambled and spread with an 11 chip barker. SYNC and SFD are internally generated. SIGNAL, SERVICE and LENGTH fields are provided by the interface 80 via a control port. SIGNAL is indicated by 2 control bits and then formatted as described. The interface 80 provides the LENGTH in μs. CRC in PLCP header is performed on SIGNAL, SERVICE and LENGTH fields.

is the variable data scrambled for normal operation.

The reference phase for the first symbol of the MPDU is the output phase of the last symbol of the header for Diff Encoding. The last symbol of the header into the scrambler 51 must be followed by the first bit of the MPDU. The variable data may be modulated and demodulated in different formats than the header portion to thereby increase the data rate, and while a switchover as indicated by the switchover point in FIG.

Turning now additionally to FIG. 1D, the

timing of the high data rate modulator 50 may be

further understood. With the illustrated timing, the

1C, occurs on-the-fly.

delay from TX\_RDY to the first Hi Rate Output Chip is ≈ ten 11 MHZ clock periods or 909.1 ns. The other illustrated quantities will be readily appreciated in view of the above description.

Referring now to FIG. 1E, the high data rate 5 demodulator 60 is further described. The high rate circuits are activated after the signal field indicates 5.5 or 11 Mbit/s operation. A carrier loop circuit is indicated by dotted lines 122, a chip detection circuit 10 is indicated by dotted line 124. At a certain time, the start phase is jammed into the Carrier NCO 61 and the start frequency offset is jammed into the Carrier Loop Filter 62. The signal is frequency translated by the C/S ROM 63 and the Complex Multiplier 64 and passed 15 to the Walsh Correlator 65. The correlator 65 output drives the Symbol Decision circuits 66, as illustrated. The output of the Symbol Decision circuits 66 are serially shifted by the parallel-in/serial-out SIPO block 67 to the descrambler portion of the PSK Demodulator and Scrambler circuit 70 after passing through the Sign Correction circuit 68 based on the last symbol of the header. The timing of the switch over desirably makes the symbol decisions ready at the correct time.

The signal is phase and frequency tracked via the Complex Multiplier 64, Carrier NCO 61 and Carrier Loop Filter 62. The output of the Complex Multiplier 64 also feeds the Carrier Phase Error Detector 76. A decision directed Chip Phase Error Detector 72 feeds the illustrated Timing Loop Filter 75 which, in turn, is connected to the Clock Enable Logic 77. A decision from the Chip Phase Error Detector 72 is used instead of early-late correlations for chip tracking since the

SNR is high. This greatly reduces the additional circuitry required for high rate operation. The 44 MHZ master clock input to the Clock Control 74 will allow tracking high rate mode chips with ± 1/8 chip steps.

5 Only the stepper is required to run at 44 MHZ, while most of the remaining circuits run at 11 MHZ. The circuit is only required to operate with a long header and sync.

Turning now additionally to FIG. 1F, a pair 10 of Walsh Correlators 65a, 65b is further described. The I\_END and Q\_END inputs from the chip tracking loop are input at 11 MHZ. The Modified Walsh Generator 81 produces the 8 Walsh codes (WO to W7) serially to sixteen parallel correlators (8 for I END and 8 for Q END). The sixteen correlations are available at a 15 1.375 MHZ rate. The Walsh Codes (WO to W7) are the same as listed in the table above for the high data rate modulator. For the 11 Mbit/s mode, the largest magnitude of I W0 to I W7 is selected by the Pick 20 Largest Magnitude circuit 81a to form I sym. formatted in Sign-Magnitude. The Magnitude is the Modified Walsh Index (0 to 7) of the largest Correlation and Sign is the sign bit of the input of the winning Correlation. The Q channel is processed in 25 parallel in the same manner. For the 5.5 Mbit/s mode, the largest magnitude of I W0 to I W7 is selected to form Isym. In this case, only I sym is output. AccEn controls the correlator timing and is supplied by timing and control circuits.

Other details of the carrier tracking loop (also known as the carrier loop circuit) and chip tracking loop are shown in FIGS. 7 and 8 of the incorporated by reference 08/819,846 patent application.

As noted above, orthogonal keying has been described. M-ary bi-orthogonal keying is one

modulation choice for high rates in the 2.4 GHz ISM band. This technique can easily be made interoperable with the existing 802.11 networks by incorporating the same preamble and header which already has a rate change mechanism. The M-ary bi-orthogonal keying (MBOK) modulation is well known to those skilled in the art.

As is known to those skilled in the art, MBOK allows multi-channel operation in the ISM band by

10 virtue of keeping the total spread bandwidth the same as the existing 802.11 standard. The spreading is actually more uniform than the 802.11 Barker words, but it has the same chipping rate and the same basic spectrum shape. The spectrum is filtered to 17 MHZ at the 3 dB points and to 35 dB beyond 22 MHZ. This allows placing three non-interfering channels in the ISM band (which is from 2.40 to 2.483 GHz) with allowance for spectral energy reduction at the band edges. With more aggressive filtering, four channels could be squeezed into the band.

MBOK is a power efficient modulation and provides good range for the higher data rates. It is robust, having good tolerance for interference and multipath. M-ary orthogonal keying (MOK) can be shown to be a generalization of many standard waveforms such as FSK.

Data enters scrambler 92a and enters 1:8 multiplexer 92b (for Walsh functions). Walsh function select

30 circuits 92c select one of eight Walsh functions. In this scheme, the spread function is picked from a set of M orthogonal vectors by the data word. Since the I and Q channels can be considered independent when coherently processed, both can be modulated this way.

35 Bi-orthogonal keying extends this by using both true and inverted versions of the spread functions. This allows the circuits to pack 8 bits into each symbol.

WO 99/49586 PCT/US99/00940

-19-

As an example, well known orthogonal vector set is the Walsh function set. It is available for 8 chip (powers of 2) vectors and has true orthogonality. Modifications to the basic set can be made by adding 5 another fixed bit pattern to it. This might be done, for example, to avoid the all 0's member of the basic set.

FIG. 1H illustrates four modulation modes of the extended modulation package. The two 802.11 1 and 2 MBps modes are shown as basically setting the polarity of the I and/or Q channel spreading function. For the 5.5 MBps mode, the incoming data is grouped into four bit nibbles where three of those bits select the spreading function out of the set of 8 while the fourth bit sets the polarity. The spreading sequence chosen then BPSK modulates the carrier by driving the I and Q modulators in parallel. To make 11 MBps modulation, the input data is grouped into two nibbles and used to modulate the I and Q channels 20 independently.

To make the modulation have the same bandwidth as an existing 802.11 DS modulation, the chipping rate can be kept at 11 Mcps while the symbol rate can be increased to 1.375 MSps. This makes the 25 overall bit rate 11 MBps. This also makes it easy to make the system interoperable with the 802.11 preamble and header. Since the spread rate remains constant, the only thing that changes when transitioning into the data from the header is the data clock rate.

MOK modulation has been shown to have slightly (1.6dB) better Eb/NO performance than BPSK due to embedded coding properties. This allows the modulation to tolerate more interference than other waveforms. Since there are more bits per symbol with 35 this modulation, it naturally requires more Es/NO than BPSK, but the increase is minimized.

10

The spectrum of this waveform is sinx/x, which is the same as the 802.11 waveform.

The multipath performance will depend on the SNR and phase distortion tolerance of the waveform.

Antenna diversity is desired to insure a reliable 11 MBps link. The high rate modulation is more susceptible to multipath interference and filter distortion than lower rate modulations would be due to the higher required SNR.

10 The MBOK modulation when used in a BPSK fashion achieves 5.5 MBps. By using the MBOK scheme on both the quadrature I and Q channels (which are independent), the basic data rate can be doubled to 11 MBps. This also allows options for lower rates which are more robust, giving fall back rates for stressed links. The excellent range that the m-ary biorthogonal keying modulation achieves is due to the fact that MBOK has better than BPSK performance.

#### Antenna Diversity Advantage

Antenna diversity is important to go about deciding which is the best antenna, such as when two antennae are situated in a circuit board. It has been known that it is possible to demodulate the data off two antennas that are typically positioned on a circuit board, such as well known to those skilled in the art. The circuits of a spread spectrum transceiver would then determine which antenna came out with the "cleaner" set of data. However, in many prior art systems, this would require two receivers. Thus, it is necessary to obtain a good diversity selection metric.

Typically, a laptop computer used in a WLAN configuration would have two antennas that are formed as rubber coated antennas, as known to those skilled in the art. These antennae could stick out from the board. There have been various designs for antenna diversity, such as antennas that pull out and turn to the side, or that permanently stick out. With two

antennas, it is necessary to determine what antenna to pick. One known way is to use the signal-to-noise ratio (SNR) to pick the required antenna.

However, in a large office environment with

many doors and walls, the environment is similar to an
echo chamber. The signal that is best for the receiver
may not be the largest signal and this largest signal
may not be the best signal element in terms of
demodulating the signal. All signs could be corrupted
by multipath. Thus, the signals subtract and could
make a signal weaker and a previous algorithm using the
SNR would be appropriate. However, if the multipath
made a more powerful, corrupted signal, then the
algorithm using an SNR to obtain the highest signal
would not be the best. The actual demodulated signal
would be a more corrupted signal, even though it had
greater energy.

It is desirable to find the least corrupt signal, and not the highest power signal. The present invention uses a correlation technique to decide what is the best, least corrupt signal to demodulate, instead of looking only at the greatest power signal as in prior art techniques.

From a correlator, one always obtains a noise signal and an impulse signal when using this particular 25 type of spread spectrum waveform that is repeated, as known to those skilled in the art, in spread spectrum technology. Echoes are obtained, and if one of the echoes is strong, the echo could be used as the desired signal. For example, because a signal is passing 30 through the wall, it could be weak. But that one signal that bounced out of the door off the wall could be a stronger signal. Each of those signals and the corrupted signal which proceeds and comes after the 35 signal could be tracked. The signal going through the wall could be the desired signal to demodulate even though it is the weaker signal.

15

20

25

The present invention comprises a method and associated circuitry that uses the taps out of the correlator to determine the better signal. example, there could be a tap of 22 samples in each of 5 the sample intervals. The sample used for demodulation is one that falls on the correlation peak in time. algorithm takes samples before the peak and samples after the peak, sums them together (compares and subtracts them from the peak so that there is a measure done with the different antennas). The cleaner is then picked.

Basically, the system looks to the left and right of reference and does a subtraction to obtain the cleaner signal. It is a diversity scheme to determine which of two antennas are better for receiving the next signal. It could also be accomplished for transmitting the next signal because if reception is good, then the path back is generally also good, although that is not always guaranteed. The metric gives an advantage to multipath corrupt environments.

As to measurements, they have been accomplished on Barker codes. It is possible to make a decision whether a Walsh or other similar signal is good not based solely on the Barker codes. possible to use an additional second antenna diversity period to refine an estimate of what is the better Thus, it is possible to improve the performance of the diversity scheme.

The advantages of antenna diversity are 30 derived from the fact that two sufficiently physically separated antennas usually result in non-completely correlated channels. The dimensions of a laptop (12") provides sufficient physical separation for significant antenna diversity performance gain, although for most 35 near term applications, only the access point and perhaps desktop PCs will have diversity to minimize cost. The coming integration of wireless network

WO 99/49586 PCT/US99/00940

-23-

hardware into laptops will isolate the user from antenna wiring.

The actual performance gain achieved is highly dependent upon the details of the operational environment. In the limit, if the channels are uncorrelated, and the best antennas accurately chosen, the mixed message rate can be raised to the power of the number of independent paths. For example, a 50% missed message rate could, with dual receive diversity, theoretically be reduced to 25%, and with dual transmit and receive diversity to 6.25%. Antenna diversity also reduces the probability of "dead spots," which are very annoying to users.

Antenna diversity complexity and performance
should track the performance of the rest of the modem.
Providing various interoperable cost/performance
options extends the breadth of feasible users (home,
office, industrial and custom products) and reduces
cost by increasing production qualitites. Examples
include a low cost non-diverse IF limited receiver to
which antenna diversity, equalizer and additional
processing could be added, depending upon the price
sensitivity of the user. Another example where the
present invention can be applied is the transceiver
shown in FIGS. 1A-1F.

Starting at the low end, the current antenna diversity metric, which optimizes signal to noise ratio (1 and 2 MBPS specification) with an IF limited signal, can be easily modified to optimize multipath performance for useful IF limited delay spreads. Accurate performance of the metric at very large delay spreads, far beyond the useful range of a limited receiver, is not necessary.

Optimizing performance at 1 and 11 MBps

requires different metrics since their susceptibility to multipath effects are vastly different. As the data rate is not known at the antenna diversity decision

20

25

30

35

time, redoing antenna diversity between the header and the start of 11 Mbps data requires no 1 or 2 Mbps specification changes while providing a very robust accurate hardware efficient metric optimized for the specific data rate. A very robust accurate hardware efficient metric can be used when the scheme uses the code word vectors (in one embodiment 8 Walsh basis vectors) received on each antenna and a correlation is performed to decide on the best correlation.

A high performance receiver which corrects for the multipath would necessarily want to minimize the processed symbol error rate. How this can be accomplished varies with the particular receive processing. Typical examples include RMS residual 15 error from an equalizer and trace back information from a maximum likelihood algorithm.

A simple access point (AP) transmit antenna diversity scheme, which can be added to receive diversity, to provide significant improvement with no hardware impact, is also set forth below.

The IF limiting low end receiver requires good multipath diversity performance for 25 to 50 ns RMS delay spreads with minimal hardware. This low end receiver will lose significant throughput with larger delay spreads. However, the diversity scheme works with higher delay spreads to choose the low delay spread antenna, if one is available.

The diversity scheme is fully compliant with the current IEEE 802.11 specifications. The diversity selection process of the present invention is best suited for the IEEE 802.11 high rate waveform.

The diversity in one aspect of the present invention is done during the Barker preamble where it is currently accomplished. Since the data rate is unknown to the receiver at the diversity decision time, the performance will necessarily be a compromise. can be accomplished as performance is acceptable at 100

-25-

ns RMS, which is beyond the useful operating RMS delay spread.

The diversity scheme can operate with an IF limiter and obtain excellent performance at all useful 5 delay spreads. Optimizing performance at 1 and 11 MBps requires different metrics. Because the data rate is not known at the antenna diversity decision time, redoing antenna diversity between the header and the start of the 11 MBps data is reasonable. The goal is 10 to minimize complexity and the additional gate count (1,000 gates).

The code word vector diversity of the present invention inserts a second antenna diversity period between the header, where the high rate is selected, 15 and the start of the high rate data. As an example, the second antenna diversity period could be a Walsh basis vector. Because no changes are necessary to the current 802.11 specification, except the rate field, this permits a plurality of code word vectors to be received on each antenna. In one aspect of the invention as an example, the code word vectors could be eight Walsh basis vectors.

The receive limiter could reduce cost by deleting the AGC function. The diversity scheme could 25 operate with differentially detected non-coherent bit sync samples. This information already exists and has been non-coherently combined to reduce its variance.

The present invention can minimize complexity and additional gate count. This has been accomplished as only approximately 500 additional gates are required for the multipath diversity metric.

An example of an IF limiter diversity bit sync metric is provided as follows:

Metric = 
$$-S_{-2chips} - S_{-1chip} + S_0 - S_{+1chip} - S_{+2chips}$$
  
or with a small loss  
Metric =  $-S_{-1chip} + S_0 - S_{+1chip} - S_{+2chips}$ 

where

20

 $S_0$  = bit sync peak sample.

The IF limiter diversity bit sync metric in accordance with the present invention is computed by subtracting a predetermined bit sync samples (such as an example four bit sync samples) a predetermined number of chips on either side of the bit sync peak from the peak (such as one and two bits). The antenna with the higher result becomes the selected antenna. Not subtracting the sample the predetermined number of chips early results in only a small performance loss.

The code word distance, a robust measure how close demodulated symbols are to making an error, can be computed by:

- Finding the minimum correlation of the
   code word vectors transmitted sequentially on one channel (I or Q).
  - 2. Finding the maximum of the absolute value of the cross-correlation of the code word vectors on both channels not including the correlation peaks above.
  - 3. Subtracting the results obtained from #2 from the results obtained from #1 above. If Walsh vectors are used, then eight Walsh basis vectors are used.
- Assuming the code word distance is an indication of message error rate, it can be used as a quick indication of antenna diversity accuracy.

Relating to this IF limiter diversity metric performance as explained before, the correlation of this non-coherent bit sync metric with Walsh distance is shown for 10 (FIG. 2) 25 (FIG. 3), 50 (FIG. 4), and 100 (FIG. 5) ns RMS. Each figure consists of 1000 trials. For the delay spreads of interest and an IF limiting receiver, this metric appears highly correlated with symbol error rate.

Relating to the code word vector diversity assumptions, higher performance receivers require an

25

30

35

antenna diversity metric with improved performance at delay spreads greater than 100 ns. This metric can be used by both higher performance IF limiting and linear receivers. It can operate with an IF limited receiver with excellent performance at all delay spreads.

Optimizing performance at 1 and 11 MBps requires different metrics. Because the data rate is not known at the antenna diversity decision time, redoing antenna diversity between the header and start 10 of the 11 MBps data is a preferred approach. Again, the goal is to minimize complexity and additional gate count.

The code word vector diversity concept inserts a second antenna diversity period between the 15 header, where the high rate is selected, and the start of high rate data. No changes to current IEEE 802.11 specification (except rate field) is required as the format of the high rate data field has not been specified, and the reception of an unspecified data rate is handled per the current specification.

The concept is to transmit the code word vectors twice (if Walsh vectors are used, eight Walsh vectors), which permits the code word vectors to be received on each antenna. By this approach, a compromise can be achieved between complexity and performance. Since the code word vectors are actually passed through the channel, de-convolution is not required for an accurate performance estimate.

The code word distance is hardware efficient as the correlators already exist for data demodulation. Implementing the minimum and maximum processing requires approximately 1000 gates.

The suggested high rate frame format, as shown in FIG. 6A, includes a new field for redoing the receive antenna diversity. This variation includes a high rate portion within the message so the decision is improved by not being based purely on the Barker

portion of the waveform. At this point, the following data rate is known. The antenna diversity can therefor be optimized for the rate. The MAC does not need to take this field into account when computing the length of the field. By using an unused bit in the header, the BBP could decode whether or not this field is included, thus permitting short 11 MBps messages to selectively delete this approximately 15 microsecond field.

- A high rate field format, as shown in FIG.

  6B, includes six new sub-fields required for redoing
  the receive antenna diversity. This implementation
  scheme assumes that you make your decision purely on
  the Barker code without any feedback from the Walsh/CCK

  15 part of the message. These sub-fields include:
  - 1. Code word distance (could be Walsh distance) for the current antenna which was selected for optimum 1 MBps operation.
- 2. Guard time for antenna switching and 20 filter decay time.
  - 3. Timing and carrier phase acquisition for the other antenna. Since the signal to noise ratio must be relatively high for 11 MBps operation, compared to 1 MBps operation, 1 to 38 chip symbols should be sufficient.
  - 4. Code word distance (could be Walsh distance) for the other antenna using the same 8 symbol sequence.
- 5. Guard time for antenna switching and filter decay time. The receiver does not need this unless the original antenna was selected, but must be included.
- 6. Timing and carrier phase acquisition for the selected antenna. This could be shortened, but is included to be conservative.

Relating to the AP protocol transmit diversity assumptions, transmit antenna diversity can

provide significant throughput improvement at little cost beyond receive diversity. A simplified access point (AP) transmit antenna diversity scheme permits a low cost improvement in throughput.

The scheme is integrated with IEEE 802.11 5 protocol. The network is "hub-spoke" having an AP and one or more stations. All traffic passes through an The AP has dual antenna diversity, stations do not (in an important scenario). The scheme works for 10 diverse and non-diverse AP's without prior knowledge by the stations. A node knows if it is an AP. An AP knows if it has dual diversity or not. The channel is stationary for several messages (the multipath spec assumes this). Assume single and multiple isolated 15 messages with acknowledgments (ACK). The probability of 1 MBps header loss is relatively low. The AP Media Access Controller (MAC) can store and process 1 bit per station for the selected antenna. One unused header bit can be used as an ACK/NAK bit. Retries occur as 20 soon as possible. A reciprocal channel is not necessary, but may be used. NAKs are only used to prevent other stations from transmitting via CCA.

Relating to the AP protocol transmit diversity, the following description explains in time a basic sequence.

- 1. AP has information to transmit to a Rx Station. The Rx Station's previously selected Tx antenna is used.
- 2. If an ACK is received, the Tx antenna will be used first for the next Tx to that Station. The robust ACK bit in the header makes this work. The Tx antenna may be modified by a later reception from the Rx Station.
- 3. If an ACK is not received, the message is quickly retransmitted on the other antenna.
  - 4. See #2.

30

- 5. If an ACK is not received, neither Tx antenna worked. This appears to the system as a missing message. The Rx Station's selected antenna remains unchanged as it was best in the past.
- 5 6. A Station has information to transmit to the AP. The AP's current HW diversity is used to select the Rx antenna.
  - 7. If the data is verified, the Rx antenna will be used for the ACK and the next Tx to that Station. The robust ACK bit in the header makes this work. The Tx antenna may be modified by a later reception from the Rx Station.
- 8. If the data is not verified, a NAK is sent on the Rx antenna and the message will be quickly retransmitted for reception on the other antenna. The Rx antenna is used for the NAK as the other may have no communication. The NAK prevents other Stations from transmitting.
  - 9. See #7.
- 20 10. If the data is not verified, neither Rx antenna worked. This appears to the system as a missed message. A NAK may be retransmitted to reduce number of control states.

The following description shows another 25 sequential process.

- 1. The station has information to transmit to an AP.
- 2. If an ACK is received, the message was received. The robust ACK bit in the header makes this work.
- 3. If an ACK is not received, the message is quickly retransmitted.
  - 4. See #2.
- 5. If an ACK is not received, neither AP Rx antenna worked. This appears to the system as a missed message.

-31-

6. AP has information to transmit to a station.

- 7. If the data is verified, an ACK is transmitted to the AP. The robust ACK bit in the header makes this work.
  - 8. If the data is not verified, a NAK is sent and the message will be quickly retransmitted. The NAK prevents other stations from transmitting.
    - 9. See #7.
- 10. If the data is not verified, neither AP Tx antenna worked. This appears to the system as a missed message. A NAK may be retransmitted to reduce number of control states.

This scheme helps the AP to station messages

15 by adding AP Tx antenna diversity, it does little for
station to AP throughput unless short probe messages
are used. Improvements can be made based on various
realistic assumptions: e.g., having the stations tell
the AP which Rx antenna to use based on their

20 receptions and a reciprocal channel assumption. This would require a change in the preamble or a change in the inter-message gap timing.

FIG. 6C illustrates a circuit portion of the high data rate demodulator 60 of FIG. 1A that

25 determines the bit sync peak sample within the packet symbol and subtracts a predetermined number of bit sync samples a predetermined number of chips on either side of the bit sync peak sample. As shown in FIG. 6C, the I and Q channel inputs pass into the three bit analog to digital converters 41 and then into time in variant matched filter correlators 94a, 94b. The correlated signals then pass into a magnitude determination

symbols. This process occurs in real time and a clocked waveform will come out in real time. The subtractor includes appropriate subtractor elements 94e

circuit 94c and into accumulator 94d that accumulates

from the earliest to the peak to the latest and appropriate addition and subtraction elements 94f, 94g as is well known to those skilled in the art. These elements can be part of the DPSK demodulator and descrambler.

## Multipath Mitigation

The present invention is also directed to high-performing, low-complexity techniques for mitigating multipath at the high data rates of 5.5 and 10 11 MBps. The following explanation of the invention centers on 11 MBps. However, the modifications required to down-scale to 5.5 MBps are straight-forward.

Multipath as described above is a recurring problem in spread spectrum communications, especially with the use of WLAN systems. Another decision metric can be used to mitigate multipath using the channel impulse response. Thus, once an antenna is chosen, such as in the decision metric described above, the signal can still be "cleaned up." In accordance with the present invention, an equalization stage is used, such as with the base band processor of the type as described above.

One problem in an aspect of the technology is
that there are two portions of one type of waveform:
(1) the preamble portion, and (2) the longer data
portion. The preamble portion includes part of the 11
chip codes that form the Barker codes, while the other
portion could form the Walsh codes that are the eight
chip codes forming the orthogonal code sequence. The
architecture that will be described can be used within
any coded portion to minimize multipath problems.
However, the method and architecture of the present
invention is described in detail with a Walsh code

WO:99/49586 PCT/US99/00940

-33-

correlator for purposes of illustration. The invention is not limited to a Walsh code correlator.

As noted above, the preamble can be used to synchronize and do antenna selection. When the processor finally obtains the data portion and begins processing as noted above with the base band processor shown in FIGS. 1A-1F, the waveform can be demodulated by the carrier tracking loop (also known as carrier loop circuit) using the NCO and C/S ROM as noted above.

10 For each chip that comes into the spread spectrum waveform, there is also a decision on that chip and a carrier recovery loop is run as noted above with reference to FIGS. 1A-1F, which illustrate an example of a base band processor that could be modified for use of the present invention.

As noted above, the transmitter sends one code word at a time and the receiver must correlate to determine the largest correlation as noted above. A problem with multipath distortion is that the chips coming into the correlator are distorted by the multipath (the echoes) coming into the receiver. The present invention is advantageous because it uses equalization to equalize out the multipath distortion. The particular type of equalizer of the present invention is a decision feedback equalizer using FIR filters. The channel impulse response can be estimated and once the multipath is determined, the system analytically computes what the taps would be. The taps can be initialized.

In one aspect of the present invention, a full equalizer is not used, but the feedback structure of the impulse response filter is only used. This feedback structure requires only adds and subtracts and decisions come in as ±1. The chip decision circuit is operative with carrier recovery and when a chip

decision is made, the chip decision that is used for the basic broad band processor is also used for the equalizer made with the carrier recovery. The finite impulse response filter is primarily known to those skilled in the art as a shift register with weighted taps. The FIR creates a local copy and resynthesizes the echo and subtracts it out and acts as an echo cancelor. Thus, the tail portion shown in FIG. 31 has been canceled. The feedback taps can be varied to change what is to be canceled.

In still another aspect of the present invention, a feed forward stage that requires a full multiplier can be added. It is not added within the loop, but filters out the head.

The signal processing techniques provide theoretical performance of less than 10% packet-errorrates at multipath spreads up to 200 nsec RMS. The invention is unique in exploiting a certain characteristic of the multipath channel other approaches ignore — statistically, the predominate channel-impulse-response energy follows the impulse response peak. Also, the present invention avoids the data-rate capacity loss which naturally occurs when the signal is burdened with other constraining waveform properties.

These strategies are shown to be advantageous when trying to achieve a high bits/Hz spectral efficiency at low complexity. The present invention works with the existing preamble or with a new short preamble. Only an accurate channel impulse response estimate is needed to configure the demodulator for data-mode tracking.

As background, the amount and types of linear distortion which the receiver must cope with are presented. For good performance the distortion must be

compensated. The compensation techniques can greatly increase complexity. The key system components including the linear distortions is illustrated in FIG. 7, showing transmitter filters 100, multipath fading 102 and receiver 104.

filters which can be used in the present invention.

The transmit filters 105 must meet a spectral mask and include a TX SAW filter 106. Limiting bandwidth

consumption is important for multiuser occupancy. The receive filters 107 limit noise, interference and control frequency translation distortion and include an RX SAW filter 108. Cost effective filters have been selected. Models of these filters have been used in performance analysis.

FIGS. 9A and 9B shows the lab-measured characteristics of the SAW filters. FIG. 9A shows the frequency response and FIG. 9B shows the impulse response. The presence of the third transit echo, a characteristic of SAW filters, is illustrated.

The resulting modulator/demodulator impulse is shown in FIG. 10 for the end-to-end modem filter response. The filters cause multiple-chip-duration distortion. This distortion is included for realistic analysis. The modem filter's impulse response is convolved with the multipath channel figures. This causes a significant smearing of the channel fingers.

The filters cause a non-trivial amount of eye closure in the scatter plot. Techniques which combat multipath help mitigate the distortion caused by the modem filters.

The exponentially-decaying Raleigh fading multipath model used to estimate performance is now discussed. FIG. 11 shows the characteristic of a

20

discrete exponentially decaying Raleigh fading channel model. The stochastic realization consists of complex Gaussian RV's at each discrete instance. This model uses many multipath components. They are finely spaced. The invention retained all energy until the tails contained only energy more than 30 dB down.

A stochastic realization for 100 nsec RMS multipath is shown in FIG. 12, which illustrates exponential decaying fading examples. The invention used 8 samples per chip. The chip rate is 11 MHZ. The impulse response typically spans 6 to 8 chips for the 100 nsec RMS spread channel. The coherent bandwidth is about 0.5 MHZ.

End-to-end effects are now discussed, which
examines the linear filtering effects extending end-toend. FIG. 13 shows a stochastic realization for the
100 nsec RMS multipath spread case. The signal has
been decimated to 1 sample/chip about the impulse
response peak. The 100 nsec RMS delay channel
typically spreads energy across 6-8 chips.

FIG. 13A shows the impulse response. FIG. 13B shows the frequency response in the Nyquist bandwidth. FIG. 13C shows the corresponding constellation.

FIG. 14 shows a stochastic realization for the 200 nsec RMS multipath spread case. FIG. 14A shows the impulse response and FIG. 14B shows the frequency response in the Nyquist bandwidth. Here the energy is typically spread across 12-16 chips. The Barker word is limited in its ability to estimate channel impulse response this long.

FIG. 15 illustrates the post cursor component as the dominant channel characteristic. The end-to-end energy spans about six times the RMS delay spread. The receiver complexity is driven by this effect.

WO 99/49586 PCT/US99/00940

-37-

Typically the channel has a small amount of precursor energy leading the impulse response peak and a lot of post-cursor energy following the peak.

Thermal noise is another important issue. Thermal noise is predominately generated in the receiver front-end and is measured by the noise figure. Propagation loss defines where the signal lies relative to the noise floor. Some environments are 1/re while others are  $1/r^4$ , where r is the TX/RX separation.

For linear processing, AGC set-up is an 10 important issue as shown in FIG. 16, where the signal power in the receiver is influenced by the communications link.

An important issue is evaluating to what 15 degree noise is important versus multipath effects. Some designs may be more noise robust but less multipath robust. Other designs may be more multipath robust but less noise robust. An issue arises concerning the importance of weighting for performance 20 in real-world situations.

In accordance with the present invention, a signal design is set forth to select a waveform for high data rate WLAN transmission. No clear cut picture exists for selecting a waveform. Engineering intuition 25 of those skilled in the art makes the ultimate selection, possibility based upon cost and extensibility issues. However, it is believed that the narrowband-equalized signaling has not been previously analyzed sufficiently to uncover strong merits in its favor.

The two traditional communication paradigms that dominate high rate 802.11 signaling viewpoints have been the bandwidth-limited and the power-limited scenarios. This is illustrated in FIG. 18. Additional 35 factors include multipath and multi-user capacity.

Using the capacity equations for signaling in additive white Gaussian Noise (AWGN), general conclusions can be drawn. Unfortunately, the present situation is complicated by other factors. Multipath is a major performance limiting impairment along with the AWGN. Also, it is desirable to have a high multi-user capacity within the bands of interest (2.4 GHz and 5 GHZ), since these are shared spectral resources. These additional factors lead to an erosion of the normal

10 "rules of thumb" known to those skilled in the art. Nevertheless, the democratic majority seeks to push higher data rates through the medium. single-user does not care how the data rate increased, just as long as the performance is good. For a single, 15 isolated TX/RX modem pair, high data rates with good symbol error rate performance can be obtained by either conserving power or conserving bandwidth. depicted in FIG. 19, showing digital modulations capacity compressions at 10<sup>-5</sup> symbol error rate. The signals (QPSK, 8 QPSK, 16 QAM) which maintain bandwidth 20 must be provided increasing Eb/No to successfully communicate. The signals which conserve TX power by operating at low Eb/No's must necessarily consume bandwidth. The waveforms proposed to the 802.11 25 committee fall within these regions. RAKE based techniques tend to fall in the BW consuming camp, while the equalized-based techniques tend to fall within the power consuming camp. By looking at the BITS/HZ axis, it is apparent that the equalizer based communications 30 conserve BW at the single user level.

A system designer looks at these issues because the designer is interested in the joint performance of all users. Most communications today occur in scarce spectral resources allocated by governments, such as the FCC in the U.S. Multiple

users must be able to operate well concurrently. Consequently, the system designer is interested in the joint capacity of the spectral band. Here, the BITS/HZ metric includes all users.

To optimize band capacity, there are two lines of attack. On approach is to conserve bandwidth at the single user level, so many single users can be packed concurrently within a band in a non-interfering fashion. A second approach is to consume bandwidth allowing users to interfere frequently, and use processing gain to reject and combat the high signal-to-interference (SIR) ratio. For a second interfering system to work well, adaptive power control has been shown to be crucial. These two viewpoints are played-out in the cellular/PCS worlds as shown in FIG. 20, showing standard 114, bandwidth 116, and processing columns 118 with TDMA and CDMA standards.

The narrowband band-capacity-optimization approach is preferred primarily because it is more difficult to maximize band-capacity by coordinating users in the wideband approach. With the wideband approach, the users spread whether or not it is needed. The CDMA springing in the 802.11 bands is too low to provide adequate processing gain. Adaptive power control needed to realize multiple access is difficult. The WLAN systems tend to be more uncoordinated than the Cellular/PCS systems for reasons that are apparent to the those skilled in the art.

The narrowband Cellular/PCS systems tend to use equalizers, while the wideband systems use the RAKE. The present invention uses an equalizer to combat multipath distortion while conserving bandwidth.

The section on capacity loss through waveform features overhead describes that certain proposed waveforms carry bandwidth consuming, data-rate limiting

features which tend to limit capacity performance. The invention proposes a waveform that is not bound by these constraints, maximizing single-user and multi-user capacity.

describe waveforms which contain certain features beyond simple information bit loading. The first waveform feature described limits intersymbol interference. This is evident in the both OFDM and RAKE (correlation based processing). In both these systems, conventionally signaling symbols must be much longer in duration than the multipath spread. The motive for this is shown in FIG. 21, which illustrates the minimizing ISI by increasing symbol duration so that the convolution smear is a small percentage of the symbol.

The channel multipath spread smears adjacent symbols into one another. This intersymbol interference (ISI) can be significant, requiring equalization to mitigate the performance loss. OFDM systems use a slow IFFT/FFT signaling rate within waveform cyclic extensions (buffering) to minimize the effect. RAKE receivers traditionally have a many chips/symbol, with long duration symbols for the same reason.

Unfortunately, the multipath spread is very long compared to practical RAKE symbol durations. Hence, under non-trivial multipath spreads, the 802.11 proposed RAKE techniques suffer significant loss from ISI. This is true even if the RAKE symbols have fairly good correlation properties.

The second waveform feature frequently sought involves good correlation properties. RAKE receivers have the best performance if the symbols are designed to have impulse autocorrelation properties and near-

30

WO 99/49586 PCT/US99/00940

-41-

zero cross correlation properties. The motive involves symbol detection through RAKE combining. The RAKE combiner does not work well unless the preceding correlation stage generates correlation outputs which 5 equal the channel impulse response, independent of the specific transmission symbol. If this feature is not true, symbol distance erosion occurs.

The drawback is the design of symbols with good correlation properties consumes bandwidth as shown in FIG. 22. A much broader bandwidth is necessary. 10 This is not a problem if the waveform already consumes much bandwidth for either CDMA or diversity enhancement through bandwidth (BW) spread beyond the coherent BW. This again is compatible with the power-limited modulation design concept. 15

Consuming bandwidth to purchase correlation properties means the bandwidth cannot be spent sending information bits. This limits the capacity of the single user, thereby limiting multi-user capacity within a band.

Another situation arises which greatly weakens the use of signals with good autocorrelation properties. This occurs when higher data rates are attempted with a base waveform. The key example here is with Lucent Technology's PPM modulation using the 11-bit Barker word. The 11-bit Barker word works well at low data rates because its autocorrelation properties are maintained. However, by attempting to load many information bits upon the 11-bit Barker word, 30 overall good properties are lost. When many bits are loaded, on the kernel pulse, distance is rapidly lost between symbols. In addition, the distortion of multipath becomes problematic. The convenience of an impulsive autocorrelation kernel is largely lost. The complex channel impulse response smears together the 35 potential Tx symbols. The quadrature signaling

20

crosstalks into one another by the imaginary channel taps, and the in-channel symbols are also distorted.

A large set of maximum likelihood correlations must be jointly examined for optimal processing. Candidate in-phase and quadrature symbols must be jointly searched, forming a 64 symbol set. This complexity is so high, sub-optimal short-cuts must be made. Also, ISI is high, even exaggerated by PPM, so it must be fought with the MLSE Viterbi equalizer.

10 After the development of the 1 and 2 MBps standard, 802.11 has been faced with upgrading to higher data rates up to 10 and 11 MBps. follows its usual pattern, once a 10 MBps standard exists, motivation for a new standard will rise for 20 MBps or 30 MBps. Most of the proposals presented are 15 fundamentally limited in data. However, the present invention allows a waveform which is extensible to 20 or 30 MBps, similar to the manner microwave links and voiceband modems have pushed higher data rates while 20 maintaining a fixed bandwidth. The present invention provides greatly enhanced user acceptance and proliferation, since infrastructure does not need to radically change for the higher rates.

The present invention uses chip-level
25 equalization, which use is motivated as shown by the
summary of the motivations of FIG. 23. Many of the
problems highlighted above for other waveforms is
avoided. As will be shown in the following sections,
this allows low-complexity, high-performance
30 architectures. In addition, if SNR is good enough,
chip-level equalization is potent (TDMA standards,
microwave links). Bandwidth is not wasted trying to
achieve good correlation properties. ISI is eliminated
so that symbol duration is freed from multipath-spread
35 considerations, and processing can be simpler.

One issue is, "Is the chip level SNR sufficiently high to allow chip-level processing, or is the processing gain of the many-chip symbol needed to realize adequate performance?" To answer this question, reference is made to FIG. 24. This figure shows the symbol-error-rate (SER) performance of the 8-chip on the I-channel and the 8-chip Walsh on the Q-channel versus the QPSK chip error rate. There is less than 2dB SNR performance difference at  $10^{-5}$ . 10 results from attempting to pack a high number of information bits on a few chips. This data packing results from trying to force many data bits through a limited bandwidth. As shown earlier in the powerlimited and bandwidth-limited capacity curves, 15 achieving high bits/Hz forces higher Eb/No's to be used.

Similar analysis could be shown for a Lucent Technology PPM waveform. With this type of example, the many bits are packed on the 11-bit Barker word. So much distance is lost that performance would be nearly as good if the QPSK chips were converted to QPSK symbols and the information bits sent directly on the QPSK.

Equalization of the present invention does

not mean that M-ary orthogonal waveforms cannot be
used. M-ary orthogonal waveforms can still be used to
provide orthogonal processing gain in thermal noise.

Alternatively, PPM waveforms could be used with chip
level equalization also. Eliminating chip level ISI

means the RCV processing architecture becomes much
easier.

Because a variety of equalizer techniques exist, it was essential to consider which type of equalizer technique to use. FIG. 25 shows a performance ranking of the most common techniques. The

matched filter bound is not an equalization technique, but rather a benchmark against which all can be compared. The present invention can use both MLSE and DFE (Decision Feedback Equalizer) equalizer to satisfy the needs of the receiver.

Training the equalizer is not a significant hurdle for 802.11 in accordance with the present invention. DFE and MLSE training is not a big hurdle for Cellular/PCS TDMA systems in the same way.

The present invention provides an efficient and simple tracking architecture for high bits/Hz efficiency. The invention exploits a channel characteristic the prior art approaches have ignored. The channel is predominately minimum phase. In accordance with the present invention, the minimum phase distortion can be eliminated with adds and subtracts using the feedback taps in a decision feedback equalizer.

The invention provides high-resolution

architecture scalability. The design implementation
can be highly tailored to meet performance or powerdraw needs. A designer is not forced to use one
specific architecture for all scenarios. A suite of
designs could be potentially made, optimizing

particular features, all with the same waveform. The
lowest complexity is provided in benign environments.

Medium complexity is provided in moderate multipath
environments. The highest complexity is reserved for
the severe multipath environments.

The waveform of the present invention is unfettered by RAKE waveform constraints. The waveform's distance properties are equivalent to other systems, which are pushing the same bits/Hz spectral efficiency. The signal is applicable to both 2.4 GHz and 5 GHz. Short preambles can be accommodated, since

WO 99/49586 PCT/US99/00940

-45-

equalizer acquisition only requires an estimate of the channel impulse response. Easy extensions provide data rates up to 20 or 30 MBps.

In accordance with several aspects of the present invention, three different architectures are presented. Naturally, the invention is not limited to such architectures. Other examples will come to the mind of those skilled in the art. These architectures work with the same transmit modulation. For 11 MBps the modulation is QMBOK. QMBOK consists of quadrature 10 M-ary biorthogonal keying. Eight bits are assigned to a symbol. Four bits select a sign on 1-of-8 Walsh symbols for each the I channel and the Q channel. The Walsh symbol can be viewed as having 8 chips. The quadrature signaling forms a QPSK chip. The following discussion will center on the 11 MBPS QMBOK waveform with QPSK chips. Fallback to 5.5 MBps will accomplished using standard MBOK on the 1-channel only, so the Walsh chip is BPSK. The chip rate is 11 MHZ.

The simplest architecture is shown in FIG. 26 and targets the low-cost, benign multipath environment. This block diagram is a basic, simplified diagram of a portion of the spread spectrum demodulator circuit shown in FIGS. 1A-1F and especially FIG. 1E. For purposes of explanation and simplicity, the basic block components are described without reference to the preceding FIGS. 1A-1F. This architecture works for 30 nsec delay spreads or less. No equalization is used. A low-cost, nonlinear, limiting IF can be used. 30 diagram includes the I/Q input 120, the carrier loop circuit 122, the chip decision circuit 124, the code word correlator, which in the illustrated embodiment is a Walsh correlator 126, and the symbol decision circuit These elements are also shown in FIG. 1E, with 128.

20

the carrier loop circuit 122 and chip decision circuit 124 shown generally by dotted outline. These elements are shown generally in FIG. 1E. A plot simulated multipath performance is shown in FIG. 27.

In accordance with the present invention, the 5 different aspects of the present invention using equalization are illustrated with increasing performance-complexity characteristics. The 10% packet-error-rate (PER) multipath performance can 10 theoretically exceed 100 nsec RMS delay spreads. Instantaneous equalizer training is achieved using only an estimate of the channel impulse response. assumed the impulse response estimate exists with 2 samples/chip, so a preferred decimation phase can be selected. This minimizes noise amplification by feed-15 forward taps in the DFE.

A decision feedback equalizer is shown schematically in FIG. 28. In multipath environments, DFE (and as explained later Viterbi) equalizer outperform to linear equalizer. The DFE performance is provided by the absence of noise amplification in the feedback stage.

Theoretically, the DFE processes two types of channel information differently. The minimum phase 25 channel components are processed by the feedback (FB) stage, illustrated by block 130, which is formed as a Finite Impulse Response Filter, as known to those skilled in the art, having feedback taps, i.e., formed as a shift register with weighted taps. The maximum 30 phase channel components are processed by the feedforward (FF) section shown by block 132. A typical impulse response for 100 nsec delay spread is shown in The peak of the impulse response usually defines a partition between the minimum-phase and 35 maximum-phase channel components. The energy in front

of the peak (precursor) is maximum phase, while the energy following the peak (postcursor) is minimum phase.

For a FIR (Finite Impulse Response) channel, 5 the minimum-phase zeros fall inside the unit circle in the Z-plane. The maximum-phase zeros fall outside the unit circle. This is demonstrated for the zeros-plot shown in FIG. 30 for the channel shown in FIG. 31. two zeros outside the unit circle correspond to the two precursor taps shown in FIG. 29. A zero falling 10 directly on the unit circle is handled by the feedback taps.

Decision feedback equalizers are usually trained using either a zero-forcing metric (ZF) or a minimum-mean-squared-error metric (MMSE) as known to those skilled in the art. Most textbooks describe the use of a training sequence with either a slow recursive algorithm (LMS) or a fast recursive algorithm (RLS). Alternatively, for the wireless world, techniques have 20 been developed for instant training using a estimate of the channel impulse response. A preamble (IS-54) or a midamble (GSM) is used with impulsive autocorrelation properties for performing the channel estimation. channel impulse response can be used to calculate the 25 DFE taps.

Most commonly, the 802.11 multipath appears as shown in the two examples of FIG. 31. In the first example, no precursor (maximum-phase) components are present. In example 1, the ideal equalizer weights contain only feedback (FB) taps and no feed forward (FF) taps. The FB taps are set equal to the channel impulse response (1 sample/chip).

Example 2 of FIG. 31 requires FF weight calculation before the FB weights can be computed. 35 Using the zero-forcing (ZF) criterion, two FF weights

15

15

20

25

30

can be solved using the matrix shown in FIG. 32. Once the channel impulse response is known, the coefficient matrix is known. Simple inversion gives the result. The two FF weights and the  $w_1$  and  $w_0$  solution is simply  $h_1$  and  $h_0$  scaled by the same complex constant. Solving for 3 FF taps is similar.

Once the FF weights have been calculated, the FB taps are derived by convolving the channel impulse response with the FF weights. The trailing taps in the output convolution become the FB taps.

To vary complexity, a designer decides how many taps are needed to obtain a desired level of performance. These options are illustrated by using only FB taps, using only 2 FF taps, and using 3 FF taps. The number of FB taps is varied in each case.

The architecture and performance for a DFE, which uses only FB taps, is shown in FIG. 33. For a QPSK signaling element, the FB FIR output computation is very simple because no multiplications are required, only additions and subtractions. The QPSK element decision is ±1±j. Basic circuit components illustrated in FIG. 26 are also present, with the addition of the feedback FIR (Finite Impulse Response) filter 130 having taps as known to those skilled in the art.

The associated multipath performance has been conservatively estimated by the present invention. A packet error is assumed whenever a stochastic channel realization has a closed-eye at the QPSK chip level. This is conservative (worst-case bound) because the correlation gain of the fast Walsh transform is ignored. The differentiation between 64 byte and 1000 byte packets is not made. This is conservative because the data pattern needed to realize an eye closure may be a small probability event.

The performance in multipath is shown in FIG.34. The number of FB taps is varied from 0, 1, 2, 4, 6, 8 and 10.

Only 6 FB taps provides <10% packet errors out to 60 nsec and <20% packet errors out to 110 nsec of RMS multipath. This is very good performance given the simplicity. For this case, only 6 complex adds (or subtracts) are required per chip. This architecture may be good enough for many target environments.

Because the FB-taps-only case makes no attempt to combat precursor multipath components, this section adds little more complexity by using two FF taps as shown in FIG. 35, where the feed forward FIR filter 132 is inserted in line to the Walsh correlator.

15 The packet error is assumed whenever a stochastic channel realization has a closed-eye at the QPSK chip level. This is conservative (worst-case bound) because the correlation gain of the fast Walsh transform is ignored. Differentiation between 64 byte 20 and 1000 byte packets is not made. This is conservative because the data pattern needed to realize an eye closure may be small probability event.

The performance in multipath for the structure of FIG. 35 is shown in FIG. 36 for 2 FF taps 25 and various FB taps. The number of FB taps is varied from 1, 2, 4, 6, 8 and 10. As shown on the graphs, only 2 FF taps and 6 FB taps provides <10% packet errors out to 80 nsec and <20% packet errors out to 120 nsec of RMS multipath. This is very good performance given the simplicity. An extra multiply is required per chip.

It is possible to use 3 FF taps. The architecture remains that shown in FIG. 35. FIG. 36 shows the packet error rate performance in multipath for 2 FF taps and the various FB tap quantity. FIG. 37

shows the packet error rate performance in multipath for 3 FF taps and various FB tap quantities.

As shown in this graph, only 3 FF taps and 6 FB taps provides <10% packet errors out to 100 nsec and <20% packet errors out to 140 nsec of RMS multipath. This is very good performance given the simplicity. Two extra multiplies are required per chip.

## Viterbi/Decision-Feedback Equalizer

The present invention also allows a 10 viterbi/decision-feedback equalizer to be used where soft decision information is fed out to the code word correlator (e.g., the Walsh correlator) to make a spread spectrum symbol decision. Viterbi algorithms have been used when processing PSK chips. U.S. Patent 15 application serial no. 09/193,256, filed November 17, 1998, by the assignee of the present invention, discloses a Viterbi algorithm and circuits. A Viterbi equalizer shifts the equalized signal soft decision off the cross correlator so that the correlator works 20 better. This is a key distinction between the present invention and the '256 patent application above, the disclosure which is hereby incorporated by reference in its entirety.

The spread spectrum system of the invention has a low enough processing gain where the spread 25 spectrum signal could almost recognize the chips The viterbi error correction code treats themselves. the multipath in a trellis. The receiver circuitry senses the memory or the multipath that the transmitter has placed on the signal. A trellis determines what 30 was most likely. The error correction code is used with the viterbi system. Thus, the multipath is actually placing the error correction code on the signal, and when the signal comes out of the transmitter and begins bouncing off walls and 35

throughout the Wlan environment, the receiver receives the preamble and analyzes and determines the signal and the coding. The circuitry uses the trellis to determine what is a transmit waveform that was coded by the multipath.

It is also possible to use a viterbi/decision-feedback equalizer. This architecture can be varied with increasing performance-complexity characteristics.

The key motive for using the Viterbi-DFE is to strongly combat the precursor distortion in the multipath channel. The feed-forward taps in a DFE are limited in their capability.

The 10s packet-error-rate (PER) multipath

15 performance can theoretically reach 200 nsec RMS delay spreads. Instantaneous equalizer training is achieved using only an estimate of the channel impulse response.

intersymbol-interference environment, the optimum
receiver is the maximum likelihood receiver. This
receiver can be implemented using the complexity
limiting Viter: algorithm for performing maximum
likelihood sequence estimation (MLSE), which is known
to those skilled in the art. A Viterbi MLSE receiver
has been used in GSM cell phones. Unfortunately at
this time, applying MLSE is too complex for an 802.11
high data rate receiver.

However, the complexity of the Viterbi-based MLSE receiver can be greatly reduced, while maintaining good performance by employing decision feedback techniques. MSLE estimation is used on the precursor portion of the channel and feedback equalization on the post-cursor portion of the channel.

The channel forms a finite state machine 35 (FSM) as shown in FIG. 38. The symbols in the delay

elements form the state. The input of a new symbol causes a state transition. The state transitions can be represented by a trellis. The received signal therefore contains memory. An optimal detector can compare the distance between the received signal and the known possible transmit transitions. The minimum distance sequence is the optimum received signal estimate.

The number of states in the trellis is equal to M<sup>L-1</sup>, for an M-ary modulation with a L-tap channel. For QSPK chips, M is 4. For a 100 nsec RMS delay spread channel, L can range to 8. This establishes 16K states. This degree of complexity cannot be readily handled. For QPSK elements, 4 branches enter and exit each state in the trellis.

FIG. 39 illustrates how decision feedback can reduce complexity to an acceptable level. If the channel FSM were cascaded with a decision feedback stage, the overall complexity would be reduced to only the complexity of the precursor taps. This is employed in the receiver.

The decisions in the receiver for the feedback stage comes from a partial traceback of the trellis as shown in FIG. 40. A full traceback is used to make the data decision, but the partial traceback fed to the FB taps is often a good estimate of the transmit symbol. Each step in a traceback is equivalent to stepping back one extra memory in the transmit symbol queue. The reliability of the estimate increases with each traceback step.

This reliability is illustrated in FIG. 41. The drawback of the reliability increase is the number of states in the trellis increases by a factor of M-ary for each extra delay.

WO 99/49586 PCT/US99/00940

-53-

The complexity in the Viterbi algorithm comes from computing the branch metrics, determining the branch survivors, identifying the best state, and performing the traceback. Memory can be traded against real-time operations.

The architecture for the Viterbi-DFE is shown in FIG. 42. The diagram shows the qualitative details. The I/Q input proceeds to the MLSE viterbi circuit 140. The carrier loop circuit 122, chip decision circuit 124 and feedback FIR 130 are operative with the MLSE viterbi circuit 140 in one branch circuit loop. A traceback SD signal passes from the MLSE viterbi circuit 140 to the Walsh correlator 126.

The performance of a 4-state trellis ViterbiDFE is shown in FIG. 43. These curves were generated using a conservative bounding technique similar to that used for the DFE. An eye closure metric was measured given the joint operation of the MLSE/DFE. Actually, the Viterbi would often resolve the instantaneous eye closure through the traceback.

The performance for a 16-state trellis Viterbi-DFE is shown in FIG. 44. These curves were generated using a conservative bounding technique similar to that used for the DFE. An eye closure metric was measured given the joint operation of the MLSE/DFE. The Viterbi would often resolve the instantaneous eye closure through the traceback.

One performance summary is shown in the Table of FIG. 45. Multipath performance is presented in 25 nsec RMS increments, ranging from 25 nsec up to 200 nsec. The minimum architecture complexity needed to achieve a 10% packet error rate is shown.

Many instances could be satisfied with 20% packet errors in a very severe environment. If this is

20

required.

acceptable, the ZF DFE with no FF Taps and FB Taps only can be used up to 75 nsec. The ZF DFE with 2 feed forward taps can be used all the way up to 150 nsec RMS spread. Also, the 4 state Viterbi-DFE can reach as far as 175 and 200 nsec RMS spreads. This greatly reduces cost and power draw by allowing the preferred packet error rate of 10% to softly degrade to 20% when conditions are severe.

The complexity of only the DFE as shown in 10 FIG. 46 will be described. It is felt the 4 state architecture will be quite reasonable.

because the decisions are OPSK.

The DFE complexity is shown in the table of FIG. 47. The FF taps require a complex multiply each. A complex multiply is 4 real multiplies and 2 real adds. The FB taps operate with only adds/subtracts

For 2 FF taps and 6 FB taps, a gate estimate is 10K gates for the DFE tracking structure, 20K for the weights training calculation and 5K for the channel impulse response estimate. These are gate deltas over the 1 and 2 MBps silicon. Probably 6 bit A/D's will be

Mitigation of multipath can require an estimate of the channel impulse response as shown in FIG. 48. The invention can use a short preamble if the channel impulse response estimate is sufficiently accurate. The 11 bit Barker may not be sufficiently accurate for large multipath spreads.

This will tend to dominate.

This patent application is related to

30 commonly assigned, co-pending patent applications
entitled, "WIRELESS LOCAL AREA NETWORK SPREAD SPECTRUM

TRANSCEIVER WITH MULTIPATH MITIGATION" and "METHOD OF
PERFORMING ANTENNA DIVERSITY IN SPREAD SPECTRUM IN

WIRELESS LOCAL AREA NETWORK" filed on the same date of the present application by the same inventors.

Many modifications and other embodiments of the invention will come to the mind of one skilled in 5 the art having the benefit of the teachings presented in the foregoing descriptions and the associated drawings. Therefore, it is to be understood that the invention is not to be limited to the specific embodiments disclosed, and that the modifications and embodiments are intended to be included within the scope of the dependent claims.

10

25

30

## THAT WHICH IS CLAIMED IS:

1. A method of demodulating a spread spectrum signal comprising the steps of:

receiving within a demodulator of a spread spectrum receiver a spread spectrum phase shift keyed (PSK) modulated information signal on a signal channel, wherein said information signal includes a sequence of data symbols formed from a plurality of high rate mode chips;

decoding a precursor portion of the signal channel and forming a multi-state trellis having a predetermined number of states;

feedback equalizing a post-cursor portion of
the signal channel with a finite impulse response
filter having feedback taps operatively connected to a
chip detection circuit that tracks high rate mode chips
and a carrier loop circuit for phase and frequency
tracking; and

spread spectrum despreading the information signal within a spread spectrum code function correlator.

- 2. A method according to Claim 1, and further comprising the step of performing a partial signal trace back of the multi-state trellis to the feedback taps of the finite impulse response filter.
- 3. A method according to Claim 1, and further comprising the step of passing a signal trace back soft decision from a Viterbi decode circuit to the spread spectrum code function correlator.
- 4. A method according to Claim 1, wherein said information signal includes a sequence of data symbols formed from a plurality of high rate mode chips, wherein said signal channel forms a finite state machine, and further comprising the step of establishing a predetermined number of states within the multi-state trellis.

5. A method of demodulating a spread spectrum signal comprising the steps of:

receiving within a demodulator of a spread spectrum receiver a spread spectrum phase shift keyed

(PSK) modulated information signal on a signal channel;

Viterbi decoding a precursor portion of the signal channel;

feedback equalizing a post-cursor portion of the signal channel; and

- spread spectrum despreading the information signal within a spread spectrum code function correlator.
- 6. A method according to Claim 5, and further comprising the step of passing a signal trace
   15 back from a Viterbi decoder to the spread spectrum code function correlator.
- 7. A method according to Claim 5, wherein said information signal includes a sequence of data symbols formed from a plurality of high rate mode
  20 chips, wherein said signal channel forms a finite state machine, and further comprising the step of establishing a predetermined number of states within a multi-state trellis.
- 8. A method according to Claim 7, and
  25 further comprising the step of comparing the distance
  between the received signal and known possible transmit
  state transitions, and determining an optimum received
  signal estimate.
- 9. A method according to Claim 7, and further comprising the step of forming a 4-state trellis.
  - 10. A method according to Claim 7, and further comprising the step of forming a 16-state trellis.
- 11. A method according to Claim 7, and further comprising the step of comparing the distance between the received signal and known possible transmit

5.

15

state transitions and determining an optimum received signal estimate.

- 12. A spread spectrum radio transceiver comprising:
- a baseband processor and radio circuit connected thereto, said baseband processor comprising,
- a demodulator for spread spectrum phase shift keying (PSK) demodulating an information signal on a signal channel, wherein said information signal
- includes data symbols formed from a plurality of high rate mode chips forming a spread spectrum information signal, said demodulator comprising
  - at least one spread spectrum code function correlator for decoding the information according to a predetermined spreading code sequence;
  - a Viterbi decoder that receives the information signal and decodes a precursor portion of the signal channel;
- a carrier loop circuit for phase and 20 frequency tracking the information signal;
  - a chip decision circuit operative with the carrier tracking loop for tracking high rate chips;
- a decision feedback equalizer formed from a

  25 finite impulse response filter operative with the chip
  decision circuit and carrier loop circuit, and having a
  plurality of feedback taps, wherein at least one
  feedback tap is selected for logical add/subtract
  operations for equalizing a post-cursor portion of the

  30 signal channel; and
  - a modulator for spread spectrum PSK modulating information for transmission via the radio circuit, said modulator comprising at least one code function encoder for encoding information according to and orthogonal code sequence.
    - 13. A spread spectrum radio transceiver according to Claim 12, wherein said at least one spread

WO 99/49586 PCT/US99/00940

-59-

spectrum code function correlator comprises a Walsh correlator.

- 14. A spread spectrum radio transceiver according to Claim 12, wherein said Viterbi decoder further comprises means for generating a trace back soft decision to the spread spectrum code function correlator.
- according to Claim 12, wherein said Viterbi decoder

  further comprises means for generating a partial trace
  back to predetermined feedback taps of said finite
  impulse response filter.
- 16. A spread spectrum radio transceiver
  according to Claim 12, wherein said carrier loop
  15 circuit comprises:
  - a carrier numerically controlled oscillator (NCO); and
  - a carrier NCO control means for selectively operating the carrier NCO based upon a carrier phase on the carrier tracking loop.
  - 17. A spread spectrum radio transceiver comprising:
  - a baseband processor and a radio circuit connected thereto, said baseband processor comprising
- a demodulator for spread spectrum phase shift keying (PSK) demodulating an information signal on a signal channel, wherein said information signal includes data symbols formed from a plurality of high rate mode chips forming a spread spectrum information signal, said demodulator comprising,
  - at least one spread spectrum code function correlator for decoding the information according to a predetermined spreading code sequence;
- a Viterbi decoder that receives the
  information signal and decodes a precursor portion of
  the signal channel;

- a decision feedback equalizer operative with said Viterbi decoder for equalizing a post-cursor portion of the signal channel; and
- a modulator for spread spectrum PSK modulating information for transmission via the radio circuit, said modulator comprising at least one code function encoder for encoding information according to a spreading code sequence.
- 18. A spread spectrum radio transceiver
  10 according to Claim 17, wherein said at least one spread spectrum code function correlator comprises a Walsh correlator.
  - 19. A spread spectrum radio transceiver according to Claim 17, wherein said Viterbi decoder further comprises means for generating a trace back soft decision to the spread spectrum code function correlator.
    - 20. A demodulator for a spread spectrum radio transceiver, said demodulator comprising:
- a demodulator circuit for spread spectrum phase shift keying (PSK) demodulating an information signal on a signal channel, wherein said information signal includes data symbols formed from a plurality of high rate mode chips forming a spread spectrum
- 25 information signal, said demodulator comprising
  at least one spread spectrum code function
  correlator for decoding the information according to a
  predetermined spreading code sequence;
- a Viterbi decoder that receives the 30 information signal and decodes a precursor portion of the signal channel;
  - a carrier loop circuit for phase and frequency tracking the information signal;
- a chip decision circuit operative with the 35 carrier loop circuit for tracking high rate chips;
  - a decision feedback equalizer formed from a finite impulse response filter operative with the chip

WO 99/49586 PCT/US99/00940

-61-


decision circuit and carrier loop circuit, and having a plurality of feedback taps, wherein at least one feedback tap is selected for logical add/subtract operations for equalizing a post-cursor portion of the signal channel.

- 21. A demodulator according to Claim 20, wherein said at least one spread spectrum code function correlator comprises a Walsh correlator.
- 22. A demodulator according to Claim 20,

  wherein said Viterbi decoder further comprises means
  for generating a trace back soft decision to the spread
  spectrum code function correlator.
  - 23. A demodulator according to Claim 20, wherein said Viterbi decoder further comprises means for generating a partial trace back to predetermined feedback taps of said finite impulse response filter.
  - 24. A demodulator according to Claim 20, wherein said carrier loop circuit comprises:
- a carrier numerically controlled oscillator 20 (NCO); and
  - a carrier NCO control means for selectively operating the carrier NCO based upon a carrier phase on the carrier tracking loop.
- 25. A demodulator for a spread spectrum 25 radio transceiver, said demodulator comprising:
- a demodulator circuit for spread spectrum
  phase shift keying (PSK) demodulating an information
  signal on a signal channel, wherein said information
  signal includes data symbols formed from a plurality of
  high rate mode chips forming a spread spectrum
  information signal, said demodulator comprising
  - at least one spread spectrum code function correlator for decoding the information according to a predetermined spreading code sequence;
- a Viterbi decoder that receives the information signal and decodes a precursor portion of the signal channel;


a decision feedback equalizer operative with said Viterbi decoder for equalizing a post-cursor portion of the signal channel.

- 26. A demodulator according to Claim 25,5 wherein said at least one spread spectrum code function correlator comprises a Walsh correlator.
- 27. A demodulator according to Claim 25, wherein said Viterbi decoder further comprises means for generating a trace back soft decision to the spread spectrum code function correlator.




SUBSTITUTE SHEET (RULE 26)








## SUBSTITUTE SHEET (RULE 26)




SUBSTITUTE SHEET (RULE 26)











F/G. 1G








SUBSTITUTE SHEET (RULE 26)


WO 99/49586 PCT/US99/00940












CODE SET (WALSH) DIVERSITY HIGH RATE FRAME FORMAT


<u></u>				RAMP 2	SONDS					
HICH BATE	5.5 OR 11 Mbps M-ary	HIGH RATE MPDU	0-32K DATA BITS	TRAILING RAMP <=2	MICROSECONDS	Oh)				
HIGH RATE	CODE SET	HIGH RATE DIVERSITY	20 TO 24 SYMBOLS (14.6 TO 17.5? µs)		ABLED 1s	= START FRAME DELIMITER (UNIQUE WORD) (F3AOh)	lry		ECONDS	
-	£ %	HEADER CRC	16 BITS		= 128 BITS OF SCRAMBLED 1s	RAME DELIN	SIGNAL = 5.5 OR 11 Mbps M-Ary	ED (00h)	Length = $0 \text{ TO } 2^{16}$ -1 Microseconds	= CCITT CRC-16 FCS
	Mbps DeBP	LENGTH	16 BITS		= 128 BIT	= START F	$= 5.5  \mathrm{OR}  1$	SERVICE = RESERVED (00h)	$= 0.702^{11}$	= CCITT C
	EEE 802.11 DS PLCP HEADEN 48 BITS @ 1 Mbps DeBPSK	SERVICE LENGTH	8 BITS		SYNC	SFD	SIGNAL	SERVICE	LENGTH	CRC
•	<del></del>	SIGNAL	8 BITS					-		
2.11 DS EAMBLE	15 PS 8	SFD	16 BITS	AMP	SONO					
IEEE 802.11 DS PLCP PREAMBLE	144 BI 1M De	SYNC	128   BITS	LEADING RAMP	<=z MICROSECONDS					

NOTE: 1 BIT OF THE HEADER COULD BE USED TO INDICATE IF THE HIGH RATE DIVERSITY WILL BE TRANSMITTED OR NOT, THIS REMOVES THE DIVERSITY TIME PENALTY FOR NON DIVERSE Rx STATIONS

1

TIMING & CARRIER PHASE SELECTED ANTENNA CHANGE ANT. (IF REQUIRED) CODE SET (WALSH) DIVERSITY HIGH RATE FIELD FORMAT GUARD SYMBOL 20 TO 24 SYMBOLS (14.6 TO 17.5 μs) HIGH RATE M-ary 8 SYMBOLS OTHER Antenna CODE SET FIG. 6B TIMING & CARRIER PHASE 1 TO 3 SYMBOLS OTHER ANTENNA ANTENNA CHANGE GUARD SYMBOL SYMBOL HIGH RATE M-ary 8 SYMBOLS CODE SET ANTENNA CURRENT










FIG. 8



DISCRETE EXPONENTIALLY-DECAYING RAYLEIGH FADING CHANNEL MODEL. A STOCHASTIC REALIZATION CONSISTS OF COMPLEX GAUSSIAN RV'S AT EACH DISCRETE INSTANCE.


FIG. 11

Š




REAL SAW FILTER CHARACTERISTICS. (a) FREQUENCY RESPONSE (b) IMPULSE RESPONSE

ľ



END-TO-END MODEM FILTER RESPONSE





EXPONENTIAL DECAYING FADING EXAMPLE. A STOCHASTIC REALIZATION FOR THE 100 NSEC RMS DELAY-SPREAD CASE IS SHOWN

WO 99/49586

18/34


100 NSEC COMBO DECIMATED TO 1 SAMP/CHIP







MODEM/CHANNEL CASCADE EXAMPLE. A STOCHASTIC REALIZATION FOR THE 100 NSEC RMS DELAY SPREAD CASE IS SHOWN.

(a) IMPULSE RESPONSE. (b) FREQUENCY RESPONSE IN NYQUIST BANDWIDTH (c) CORRESPONDING CONSTELLATION.






POST CURSOR COMPONENT IS THE DOMINATE CHANNEL CHARACTERISTIC FIG. 15



SIGNAL POWER IN THE RECEIVER IS INFLUENCED BY THE LINK FIG. 16



#### AWGN PARADIGMS

- 1. BANDWIDTH LIMITED
- 2. POWER LIMITED

#### **ADDITIONAL TWISTS**


- 1. MULTIPATH
- 2. MULTI-USER CAPACITY



- COMPLEX MIXTURE
- NO SIMPLE SOLUTION
- ADAPTIVE TAILORING TO SCENARIO DESIRED

THE DOMINATE HIGH-RATE 802.11 SIGNALING VIEWPOINTS

FIG. 18



DIGITAL MODULATIONS CAPACITY COMPARISONS AT 10<sup>-5</sup> SYMBOL ERROR RATE

FIG. 19

_114	_116	
STANDARD	BANDWIDTH	PROCESSING
TDMA IS-54/IS-136 GSM	NARROWBAND (SNR>10dB)	DFE OR VITERBI EQUALIZER
CDMA IS-95	WIDEBAND (SIR LOW)	RAKE

CELLULAR/PCS SIGNALING PARADIGMS


#### TSYM>>MULTIPATH SPREAD TO AVOID ISI

SYMK SYMK+1

CONNOLVE () CHANNEL

MINIMIZING ISI BY INCREASING SYMBOL DURATIION SO THE CONVOLUTION SMEAR IS A SMALL PERCENTAGE OF THE SYMBOL

FIG. 21




GOOD CORRELATION PROPERTIES COMSUME BANDWIDTH WHICH LIMITS THE BITS/Hz DATA-RATE CAPACITY

FIG. 22

- IF SNR IS GOOD ENOUGH, CHIP-LEVEL EQUALIZATION IS POTENT (TDMA STANDARDS, MICROWAVE LINKS)
- DOES NOT WASTE BANDWIDTH TRYING TO ACHIEVE GOOD CORRELATION PROPERTIES
- ELIMINATES ISI, SO SYMBOL DURATION IS FREED FROM MULTIPATH-SPREAD CONSIDERATIONS
- PROCESSING CAN BE SIMPLER

**KEY ADVANTAGES** 

WO 99/49586 PCT/US99/00940




A COMPARISON OF SYMBOL ERROR RATE FOR SYMBOL LEVEL VERSUS CHIP LEVEL PROCESSING

FIG. 24

#### **EQUALIZER PERFORMACE**


MATCHED MLSE DECISION LINEAR
FILTER > (VITERBI) > FEEDBACK > EQUALIZER
BOUND EQUALIZER

## **EQUALIZER PERFORMANCE COMPARISONS**




ARCHITECTURE FOR THE NO-EQUALIZER CANONICAL FORM

FIG. 26




MULTIPATH PERFORMANCE FOR THE ARCHITECTURE SHOWN IN FIG. 26

FIG. 27



THE STRUCTURE OF A DECISION FEEDBACK EQUALIZER. THE FRONT END IS THE FEED-FORWARD SECTION, AND THE BACK-END IS THE FEEDBACK SECTION

FIG. 28




TWO TAP FEED-FORWARD DFE ZF WEIGHT CALCULATION


FIG. 32

SUBSTITUTE SHEET (RULE 26)


25/34



TYPICAL END-TO-END IMPULSE RESPONSE AT 100 NSEC RMS DELAY FIG. 29




CHANNEL ZEROS FOR THE IMPULSE RESPONSE SHOWN IN FIG. 29 *FIG. 30* 




CHANNEL DIAGRAM EMPHASIZING TYPICAL CHARACTERISTICS

FIG. 31




FB TAPS ONLY DEMODULATION ARCHITECTURE

FIG. 33




PACKET ERROR RATE PERFORMANCE IN MULTIPATH FOR VARIOUS FB TAP QUANTITIES. THIS DATA WAS CALCULATED USING A WORST-CASE BOUND-CHIP EYE CLOSURE.

FIG. 34




ARCHITECTURE INCLUDING FEEDFORWARD DFE TAPS


FIG. 35




PACKET ERROR RATE PERFORMANCE IN MULTIPATH FOR 2 FF TAPS AND VARIOUS FB TAPS QUANTITIES. THIS DATA WAS CALCULATED USING A WORST-CASE BOUND-CHIP EYE CLOSURE.




PACKET ERROR RATE PERFORMANCE IN MULTIPATH FOR 3 FF TAPS AND VARIOUS FB TAPS QUANTITIES. THIS DATA WAS CALCULATED USING A WORST-CASE BOUND-CHIP EYE CLOSURE.




FINITE STATE MACHINE CHANNEL VIEWPOINT.
(a) THE CHANNEL IMPULSE RESPONSE FORMS FSM (b) A REPRESENTATIVE TRELLIS



REDUCING THE COMPLEXITY OF THE FINITE-STATE-MACHINE THROUGH DICISION FEEDBACK




A PARTIAL TRACEBACK IS USED TO FEED THE DECISION FEEDBACK STAGE FIG. 40




Eb/No (dB)
VITERBI DFE PERFORMANCE VARIATION WITH INCREASING
PARTIAL TRACEBACK DELAYS

FIG. 41




ARCHITECTURE FOR THE VITERBI-DFE FIG. 42



MULTIPATH-SPREAD PERFORMANCE CURVES FOR THE 4 STATE VITERBI-DFE FIG. 43






MULTIPATH-SPREAD PERFORMANCE CURVES FOR THE 16 STATE VITERBI-DFE FIG. 44

RMS MULTIPATH SPREAD	10 % PER	20 % PER
25	ZF DFE, 1 FB TAP	
50	ZF DFE, 2 FB TAPS	
75	ZF DFE, 2 FF AND 4 FB TAPS	ZF DFE, 4 FB TAPS
100	ZF DFE, 3 FF AND 6 FB TAPS OR 4 STATE VITERBI-DFE, 4 FB TAPS	ZF DFE, 2 FF AND 4 FB TAPS
125	4 STATE VITERBI-DFE, 6 FB TAPS	ZF DFE, 2 FF AND 6 FB TAPS
150	4 STATE VITERBI-DFE, 8 FB TAPS OR 16 STATE VITERBI-DFE, 4 FB TAPS	ZF DFE, 2 FF AND 8 FB TAPS
175	16 STATE VITERBI-DFE, 7 FB TAPS	4 STATE VITERBI-DFE, 7 FB TAPS
200	16 STATE VITERBI-DFE, 8 FB TAPS	4 STATE VITERBI-DFE, 8 FB TAPS

PACKET ERROR RATE PERFORMANCE



nff: # OF COMPLEX FF TAPS nfb: # OF COMPLEX FB TAPS # OF REAL MULTS: 4nff/CHIP

# OF REAL ADDS: (2 nFF + 6 nFB)/CHIP


# OF COMPARES: 2/CHIP

THE BASIC DFE STRUCTURE WITH MATH OPERATIONS/CHIP

FIG. 46

FUNCTION	GATE COUNT		
DFE TRACKING STRUCTURE	10K		
DFE WEIGHT CALCULATION	20K		
CIR ESTIMATION	5K		
TOTAL	35K		

GATE COUNT COMPLEXITY FOR 2 FF TAPS AND 6 FB TAPS DFE FIG. 47



A CHANNEL IMPULSE RESPONSE SHOWING AMPLITUDE AND PHASE INFORMATION